

Approved as to
form only:
AKR
Date: 7-2-13

CITY OF CHEYENNE
CONTRACT MODIFICATION

Contract Modification: No. 1
Project: E. Pershing Blvd. Reconstruction Project (Phase IV)
Project Number: 130000
Contract Number: 5921
Contractor: Reiman Corporation
Date Prepared: July 2, 2013

The above referenced contract is amended or modified as set forth in the following and these amendments and modifications of the plans and specifications are agreed to by the parties. All other aspects of the original agreement remain unchanged and in full force and effect.

I. Description of Changes

This modification modifies Contract No. 5921 with Reiman Corporation to add an additional block (600 East) of repaving to the E. Pershing Blvd. Reconstruction Project to address several significant potholes just outside of the current project limits. The extension in project limits has been approved by the Federal Highway Administration and WYDOT. This modification also changes the gradation on the asphalt oil to polymer modified oil, which should yield increased pavement life. This project was originally set up with pay items for fuel and oil adjustment, whereby the risk of changes in oil prices is shared between the City and the Contractor. The Contractor declined the option for the fuel adjustment. This modification eliminates the pay items for the fuel adjustment and applies the money saved against the total cost of this modification.

II. New Contract Items

Item No.	Description	Unit	Unit Price	Est. Quantity	Est. Cost
	MOBILIZATION	LS	\$ 9,600.00	1	\$ 9,600.00
202.03317	MILLING CONCRETE	SY	\$ 1.55	2463	\$ 3,817.65
202.03430	REMOVAL OF SIDEWALK	SY	\$ 4.25	24.4444	\$ 103.89
202.03446A	REMOVAL OF CURB AND GUTTER ADJACENT TO CONCRETE PAVEMENT	LF	\$ 6.20	482	\$ 2,988.40
202.03455	REMOVAL OF DOUBLE GUTTER	SY	\$ 9.00	77.25	\$ 695.25
301.01080	CRUSHED BASE	TON	\$ 17.50	47.3078	\$ 827.89
401.02000	HOT PLANT MIX	TON	\$ 79.75	280	\$ 22,330.00
401.10000A	ASPHALT PATCHING	SY	\$ 36.25	8	\$ 290.00
404.01000	PLANT MIX WEARING COURSE	TON	\$ 93.20	105	\$ 9,786.00

407.01000	TACK COAT	TON	\$ 776.00	0.61575	\$ 477.82
411.01010	GLASS FIBER REINFORCED PAVING FABRIC	SY	\$ 8.20	2463	\$ 20,196.60
414.01050	CONCRETE PVMT (10 in)	SY	\$ 61.00	4.25	\$ 259.25
608.10200	SIDEWALK (CONC)	SY	\$ 30.65	24.4444	\$ 749.22
609.10200	CURB AND GUTTER TYPE A	FT	\$ 17.00	482	\$ 8,194.00
609.10700	DOUBLE GUTTER	SY	\$ 40.00	73	\$ 2,920.00
620.07010	ADJUSTMENTS, VALVE BOXES	EA	\$ 300.00	5	\$ 1,500.00
625.12000	MANHOLE ADJUSTMENT	EA	\$ 363.00	1	\$ 363.00
702.70001A	4 in STRIPE, EPOXY	LF	\$ 1.07	1164	\$ 1,245.48
999.15000	ADJUSTMENT FOR MOTOR FUEL (DIESEL)	\$\$	\$ 1.00	-25000	\$ (25,000.00)
999.16000	ADJUSTMENT FOR MOTOR FUEL (UNLEADED)	\$\$	\$ 1.00	-10000	\$ (10,000.00)
999.22000	ADJUSTMENT FOR PERFORMANCE GRADED ASPHALT BINDER	\$\$	\$ 1.00	-50000	\$ (50,000.00)
	TEMPORARY TRAFFIC CONTROL	LS	\$ 3,000.00	1	\$ 3,000.00
	DETECTABLE WARNING DEVICES	EA	\$ 90.00	6	\$ 540.00
	CHANGE ASPHALT GRADATION TO PG70-28	TON	\$ 12.55	6200	\$ 77,810.00

TOTAL \$ 82,694.45

III. Schedule

No Change in schedule. Completion is scheduled for fall of 2013.

IV. Summary

Original Contract Amount	\$3,651,937.25
Previous Modifications	\$0.00
Contract Amount Prior to this Modification.....	\$3,651,937.25
This Modification	\$82,694.45
New Contract Amount	\$3,734,631.70

V. Approvals

DATE: _____

City of Cheyenne

Mayor Richard L. Kaysen

/_____
/ATTEST: City Clerk Carol A. Intlekofer

Recommend approval by City Project Manager

Recommended by Consultant

/_____
/Accepted by Contractor